

EXECUTIVE SUMMARY FOR PROPOSED ROUGH STONE QUARRY CATEGORY – B1 (CLUSTER AREA – 14.70.6 Ha.)

(Submitted for Public Hearing as per the provisions of EIA Notification 2006 & its amendments thereof)

APPROVED TOR No. TO25B0108TN5282049N, Dated: 26/08/2025 (File No. 12432)

PROPOSED QUARRY LEASE DETAILS	
SURVEY NOS	10/1 (BLOCK-6)
VILLAGE	PADALUR (EAST)
TALUK	ALATHUR
DISTRICT	PERAMBALUR
EXTENT	2.20.0 Ha
PROPOSED PRODUCTION FOR TEN YEARS	5,92,975 m ³ OF ROUGH STONE
LAND	GOVERNMENT LAND

(Sector No. 1(a) (Sector no.1 as per NABET)

Category of the Project: B1 Cluster Mining, Total Cluster Area – 14.70.6 Ha
Baseline Monitoring Period – March to May 2025

APPLICANT

M/s. SR Mines and Minerals

Flat No.2/1, Room No.4, Ramanujam Building, V.N Nagar, Karur Bypass road,
Trichy - 620 002

ENVIRONMENTAL CONSULTANT	LABORATORY
M/s. GLOBAL MINING SOLUTIONS (NABET Accredited & ISO 9001 Certified Consultant) Plot No. 6, S.F.No. 13/2, A2, VS City, RC Chettyapatty, Kottamettupatty, Omalur, Salem, Tamil Nadu – 636 455. NABET Accreditation No: NABET/EIA/23-26/SA 0241, Valid Until - 03.02.2026. Contact: 97502 23535 & 94446 54520 Email: infoglobalmining@gmail.com, globalminingsolutionssalem@gmail.com	M/s. SHRIENT ANALYTICAL & RESEARCH LABS PRIVATE LIMITED (NABL Accredited Testing Laboratory) Valid Until -29.09.2029 #416/15, Dhargas Road, Perungalathur, West Tambaram, Chennai, Tamil Nadu, India.

EXECUTIVE SUMMARY

1.1 INTRODUCTION

Environmental Impact Assessment (EIA) as a tool used to identify the environmental, social and economic impacts of a project prior to decision-making. It aims to predict environmental impacts at an early stage in project planning and design, find ways and means to reduce adverse impacts, shape projects to suit the local environment and present the predictions and options to decision-makers.

This proposal is towards obtaining environmental clearance for Rough Stone Quarry located at S.F. No. 10/1 (Block - 6) of Padalur Village, Alathur Taluk, Perambalur District, Tamil Nadu State for production capacity of 5,92,975 m³ of Rough Stone for the period of 10 years with ultimate depth up to 56 m Above Ground Level. The mining plan has prepared and same was approved by Assistant Director, Department of Geology and Mining, Perambalur, vide ROC. No. 128/G&M/2025, Dated 12.05.2025.

As per EIA notification, 2006 and its subsequent amendments the proposed "Rough Stone Quarry of **"M/s. S R Mines and Minerals"** is falls under Schedule 1(a) Mining of Minerals. It is further classified under Category B1 due to the overall extent of cluster area is 14.70.6 Ha which is >5 Ha. The ToR for the preparation of EIA/EMP was approved vide ToR identification number TO25B0108TN5282049N, dated: 26.08.2025. This report has been prepared in line with the approved TOR for maximum excavation of 5,92,975 m³ of Rough Stone for the period of 10 years with ultimate depth up to 56 m Above Ground Level.

S.No.	Description	Status/Remarks
1.	Sector	1(a), non-coal mining
2.	Category of the project	B1
3.	Proposed mineral	Rough Stone
4.	Type of Lease	Fresh
5.	Extent of the lease	2.20.0 Ha.

Draft EIA EMP report of Proposed Rough Stone Quarry of M/s. SR Mines and Minerals, over an extent of 2.20.00 Ha in S.F. No. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu

6.	Proposed depth of Mining	56 m AGL
7.	Method of mining	Opencast Mechanized
8.	Proposed lease period	10 Years
9.	Proposed Environmental Clearance	10 Years
10.	Proposed production quantity for Five years	Rough Stone – 5,92,975 m ³

M/s. S R Mines and Minerals is an individual with sound experience in the identification, quarrying and marketing of Rough Stone. The proposed land is a Government land and attached as **Annexure 6**.

1.2 LOCATION

The proposed Quarry Lease area is situated at S.F.Nos. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu State. The area lies in the north latitude of 11°06'48.23"N to 11°06'52.72"N and eastern longitude of 78°50'36.17"E to 78°50'42.96"E with Survey of India Topo Sheet No. 58 I /16. To conduct the study, the proposed mine lease area (core zone) and an impact zone of 10 km radius (called buffer zone) around the proposed mine site were considered. The EIA report is based on three months baseline data (i.e. March 2025 to May 2025)

1.3 GEOLOGY

The rock type noticed in the area for lease is Charnockite which contains mostly Quartz and Feldspar with some ferromagnesian minerals. The Charnockite is part of peninsular Gneisses, a high grade metamorphic rock. The strike of the Charnockite formation is N30°W-S30°E with vertical dipping

1.4 PROJECT DESCRIPTION

This is a proposed Rough Stone by Opencast Mechanized mining method with drilling and blasting. The quarrying is restricted up to a depth of 56m AGL. The geological reserves are estimated to be Rough Stone are 9,81,875 m³. The mineable reserve calculated by deducting safety distance and bench loss. The mineable reserves are

Draft EIA EMP report of Proposed Rough Stone Quarry of M/s. SR Mines and Minerals, over an extent of 2.20.00 Ha in S.F. No. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu

5,92,975 m³ of Rough Stone which will be recovered at the rate of 100% recovery upto a depth of 56m AGL for the period of 10 years.

- It is proposed to quarry out rough stone with 5m bench height, 5m width with overall slope is 47° using Open cast Mechanized method. The quarry operation involves shallow jack hammer drilling, slurry blasting, excavation, Loading and transportation of Rough Stone.
- There is no overburden anticipated during entire rough stone & Gravel quarrying operation.

S.No.	Type of Detail	Description
1	Sector	1(a) Non coal mining
2	Fresh/Existing project	The applied lease area is Fresh lease
3	Category	B1
4	Nature of mineral	Rough Stone
5	Production	Rough Stone – 5,92,975 m³
6	Life	10 years
7	Waste generation and management	There is no overburden anticipated during the quarrying operation. Hence, no waste generation.
8	Bench height and width	Height and Width – 5m
9	Ultimate pit depth	56 m AGL
10	End use	Rough Stone will be loaded into tippers to needy buyers for producing aggregates, M-sand.

1.5 PROJECT REQUIREMENTS

The requirements of the project is given below.

S.No.	Nature of requirement	Description
1	Water requirement	Total water requirement of 3.0 KLD which will be procured from the outside agencies. 1.0 KLD drinking and domestic water requirement, green belt development is 1.0 KLD and dust suppression is 1.0 KLD.

Draft EIA EMP report of Proposed Rough Stone Quarry of M/s. SR Mines and Minerals, over an extent of 2.20.00 Ha in S.F. No. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu

2	Power requirement	No electricity is needed for mining operations, for office demands, it will be met from the state grid.
3	Manpower requirement	29 Nos.
4	Financial requirement	Total EMP Cost for 10 years is 36.99 lakhs i.e., Rs.9.47 Lakhs of Capital + Recurring cost Rs. 27.52 lakhs for 10 years
5	Funds for Socio economic development	INR 5 Lakhs is allocated for CER activities.

1.6 DESCRIPTION OF LEASE AREA

The features in the study area is given below.

Description of the lease area		
S.No.	Areas	Distance from project site
1	Areas protected under international conventions, national or local legislation for their ecological, landscape, cultural or other related value	Nil within 15km radius
2	Areas which are important or sensitive for ecological reasons	
A	Wetlands, water courses or other water bodies,	Tank-150m(SW), Tank-260m(SE), Maruthandi Lake – 1.65km (W), Therani Big Lake-3.16Km(E), Pudukurichi Lake – 2.80 km (NE), Nanthai River- 3.60 km (SW), Uppar River- 4.80 km (SE)
B	Coastal zone, biospheres,	Nil within 10km radius
C	Mountains, forests	Naranmangalam R.F. – 3.60 km (NW), Velur R.F. – 5.50 km (NW), Nedungur R.F. – 3.80 km (SW), Muniyankurchi R.F. – 4.50 km (SW), Siruvachur R.F. – 5.80 km (NW)
3	Areas used by protected, important or sensitive species of flora or fauna for breeding, nesting, foraging, resting, overwintering, migration	Nil within 15km radius
4	Inland, coastal, marine or underground waters	Nil within 15km radius
5	State, National boundaries	Nil within 15km radius

Draft EIA EMP report of Proposed Rough Stone Quarry of M/s. SR Mines and Minerals, over an extent of 2.20.00 Ha in S.F. No. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu

6	Routes or facilities used by the public for access to recreation or other tourist, pilgrim areas	Nil within 15km radius
7	Defense installations	Nil within 15km radius
8	Nearest Town	Ariyalur – 25.3 km (E)
9	Areas occupied by sensitive man-made land uses (hospitals, schools, places of worship, community facilities)	Perambalur
10	Areas containing important, high quality or scarce resources (ground water resources, surface resources, forestry, agriculture, fisheries, tourism, minerals)	Nil
11	Areas already subjected to pollution or environmental damage. (those where existing legal environmental standards are exceeded)	Nil
12	Areas susceptible to natural hazard which could cause the project to present environmental problems (earth quakes, subsidence, landslides, erosion, flooding or extreme or adverse climatic conditions) similar effects	No. The area is not prone to earthquakes, floods, etc.

The baseline data collection for meteorology, air, water, noise and soil environments have been carried out during March to May 2025. Air, water, noise and soil samples are collected and analyzed through NABL accredited lab.

1.7 AIR ENVIRONMENT

The air monitoring has been carried out in 7 locations and the results are given below.

S.NO	Location Code	Monitoring Locations	Latitude and longitude
1	A1	Within Mine Lease area	11° 6'50.29"N & 78°50'39.52"E
2	A2	Sridevi Mangalam	11° 6'45.19"N & 78°48'6.12"E
3	A3	Near Therani Big Lake	11° 6'47.20"N 78°52'9.17"E
4	A4	Padalur West	11° 5'41.47"N & 78°49'45.65"E
5	A5	Alathur	11° 7'36.71"N & 78°50'15.75"E
6	A6	Pudhukkurichi	11° 8'5.47"N & 78°51'53.17"E
7	A7	Padalur	11° 6'17.30"N & 78°50'41.19"E

Draft EIA EMP report of Proposed Rough Stone Quarry of M/s. SR Mines and Minerals, over an extent of 2.20.00 Ha in S.F. No. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu

Results of Air sampling Analysis in 7 locations

S.NO	Parameters	PM10			PM2.5			SO2			NO2		
	Locations	Min	Avg	Max	Min	Avg	Max	Min	Avg	Max	Min	Avg	Max
1	A1 - Within Mine Lease area	52.7	64.3	75.3	25.3	30.9	36.1	5.2	6.4	7.7	8.2	9.4	10.4
2	A2 - Sridevi Mangalam	46.7	53.4	59.5	22.4	25.6	28.6	5.8	7.0	8.2	8.9	10.0	11.0
3	A3 - Kolakkanatham	45.7	49.8	56.5	21.0	23.4	26.7	5.9	7.1	8.2	9.2	10.5	11.8
4	A4 - Padalur West	47.8	53.4	59.1	21.8	25.3	29.4	4.2	5.4	6.6	8.6	9.8	10.9
5	A5 - Alathur	41.0	45.7	51.3	19.3	22.0	24.7	3.6	4.9	6.2	7.8	9.0	10.1
6	A6 - Pudhukkurichi	44.3	50.0	57.2	21.0	23.7	27.1	3.8	4.8	5.5	6.2	7.3	8.5
7	A7 - Padalur	42.3	47.0	53.3	20.2	22.4	25.4	3.6	4.6	5.7	6.9	8.1	9.2
	CPCB NAAQS 2009	100			60			80			80		
All Value in µg/m3													

All the values of pollutant concentrations were found to be within the NAAQs Standards.

1.8 WATER ENVIRONMENT

Results of Ground Water sampling Analysis in 7 locations

Results of Ground Water Analysis									Standards as Per IS 10500: 2012	
									Acceptabl e Limits	Permissibl e Limits
		W1	W2	W3	W4	W5	W6	W7		
1	Odour	Agreeabl e	Agreeabl e	Agreeabl e	Agreeabl e	Agreeabl e	Agreeabl e	Agreeabl e	Agreeable	Agreeable
2	Turbidity	<1	<1.0	<1.0	<1	<1	<1	<1	<1	<5.0
3	pH at 25 °C	7.92	7.84	7.19	7.91	7.45	7.77	7.36	6.5- 8.5	No Relaxation
4	Electrical Conductivit y	524.6	1665	1975.0	2068.0	1286.0	1989.0	2137.0	-	-
5	Total Dissolved Solids	315	1002	1186	1240	772	1194	1282	500	2000
6	Total hardness as CaCO ₃	174	354	392	424	235	385	454	200	600
7	Calcium as Ca	43.6	64.4	84	96.8	57.6	83.2	102	75	200
8	Magnesium as Mg	15.6	46.3	43.7	43.7	21.8	42.5	47.5	30	100
9	Calcium as CaCO ₃	109	161	210	242	144	208	256	-	-

Draft EIA EMP report of Proposed Rough Stone Quarry of M/s. SR Mines and Minerals, over an extent of 2.20.00 Ha in S.F. No. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu

10	Magnesium as CaCO ₃	65.0	193	182	182	91.0	177	198	-	-
11	Total alkalinity as CaCO ₃	158	327	380	399	260	376	392	200	600
12	Chloride as Cl ⁻	74.8	342	365	380	241	363	510	250	1000
13	Free Residual chlorine as Cl ⁻	BDL(D.L-0.2)	BDL(D.L-0.2)	BDL(D.L-0.2)	BDL(D.L-0.2)	BDL(D.L-0.2)	BDL(D.L-0.2)	BDL(D.L-0.2)	0.2	1
14	Sulphates as SO ₄ ²⁻	55.4	270	342	355	206	338	212	200	400
15	Iron as Fe	0.08	0.12	0.11	0.12	0.04	BDL(D.L-0.01)	0.03	0.3	No Relaxation
16	Nitrate as NO ₃	BDL(D.L-1.0)	2.14	4.65	5.23	4.32	5.62	5.51	45	No Relaxation
17	Fluoride as F	0.15	0.48	0.55	0.62	0.42	0.63	0.58	1	1.5
18	Manganese as Mn	BDL(D.L-0.05)	BDL(D.L-0.05)	BDL(D.L-0.05)	BDL(D.L-0.05)	BDL(D.L-0.05)	BDL(D.L-0.05)	BDL(D.L-0.05)	0.1	0.3

All the values were found to be within permissible limits

Surface Water Analysis Results

		W1	W2	W3	Surface water standards (IS 2296 Class-A)
1	Odour	Agreeable	Agreeable	Agreeable	-
2	Turbidity	<1	<1.0	<1.0	1
3	pH at 25 °C	7.52	7.94	7.85	6.5-8.5
4	Electrical Conductivity	218.6	167.9	192.3	-
5	Total Dissolved Solids	132	102	115	500
6	Total hardness as CaCO ₃	47.2	35.2	42.5	300
7	Calcium as Ca	10.56	10.36	9.8	80.1
8	Magnesium as Mg	4.99	2.23	4.3	24.28
9	Calcium as CaCO ₃	26.4	25.9	24.5	-
10	Magnesium as CaCO ₃	20.8	9.30	18.0	-
11	Total alkalinity as CaCO ₃	45.6	37.2	42.2	-
12	Chloride as Cl ⁻	42.8	40.8	39.8	250
13	Free Residual chlorine as Cl ⁻	BDL(D.L-0.2)	BDL(D.L-0.2)	BDL(D.L-0.2)	0.2
14	Sulphates as SO ₄ ²⁻	15.2	16.9	16.1	400

Draft EIA EMP report of Proposed Rough Stone Quarry of M/s. SR Mines and Minerals, over an extent of 2.20.00 Ha in S.F. No. 10/1 (Block-6), Padalur (East) Village, Alathur Taluk, Perambalur District, Tamil Nadu

15	Iron as Fe	0.15	0.12	0.1	0.3
16	Nitrate as NO ₃	BDL(D.L-1.0)	2.14	1.95	20
17	Fluoride as F	0.21	0.45	0.42	1.5
18	Manganese as Mn	BDL(D.L-0.05)	BDL(D.L-0.05)	BDL(D.L-0.05)	0.1
19	COD	BDL(D.L-4.0)	BDL(D.L-4.0)	BDL(D.L-4.0)	-
20	BOD	BDL(D.L-2.0)	BDL(D.L-2.0)	BDL(D.L-2.0)	2
21	TSS	22.0	12.0	10.0	-
22	DO	5.8	6.1	6.3	6

1.9 NOISE ENVIRONMENT

Noise levels were measured in 7 locations and the results are given below.

Monitoring Location	N1	N2	N3	N4	N5	N6	N7
DAY EQUIVALENT	52.8	50.0	49.1	47.9	45.1	49.4	50.8
NIGHT EQUIVALENT	40.3	38.3	41.9	41.1	37.5	43.3	39.2
DAY & NIGHT EQUIVALENT	51.2	48.4	47.8	46.5	43.7	48.2	49.2
Limits as per MoEFCC Day equivalent - 55 dB (A); Night equivalent - 45 dB (A); Work zone Exposure in 8 hr - 90 dB (A)							

1.10 SOIL ENVIRONMENT

Soil samples are collected from 7 locations and the results are given below.

S.No	Parameters	S1	S2	S3	S4	S5	S6	S7
1	pH at 25 °C	7.32	7.94	8.06	7.95	7.89	8.12	7.92
2	Electrical Conductivity	175.6	290.8	220.4	273.5	190.2	295.6	265.7
3	Dry matter content	95.32	96.52	97.21	86.54	97.25	93.67	92.58
4	Water Content	4.68	3.48	2.79	13.46	2.75	6.33	7.42
5	Organic Matter	0.75	0.95	0.82	1.32	0.77	0.95	1.03
6	Soil texture	Silty Clay loam	Silty Clay	Silty Clay	Clay	Silty Clay	Silty Clay	Silty Clay
7	Grain Size Distribution							
	i. Sand	15.52	10.42	8.55	17.05	13.22	10.79	7.89
8	ii. Silt	45.37	44.33	42.75	38.97	42.76	45.66	41.32
9	iii. Clay	39.11	45.25	48.7	43.98	44.02	43.55	50.79
10	Phosphorous as P	1.35	1.62	1.24	1.67	1.36	1.61	1.74
11	Sodium as Na	304	322	346	498	535	420	396
12	Potassium as K	580	664	735	904	1030	634	652
13	Total Nitrogen	272	405	146	205	254	312	175
14	Total Sulphur	BDL(D.L .0.02)	BDL(D .L.0.0 2)	BDL(D. L.0.02)	BDL(D.L. 0.02)	BDL(D.L. 0.02)	BDL(D.L. 0.02)	BDL(D.L. 0.02)
15	Water Holding Capacity	42	38	40	41	42	40	42
16	Porosity	18.9	19.4	17.9	17.1	18.9	18.2	17.3

1.11 BIOLOGICAL ENVIRONMENT

FLORA

For measuring the extent of flora present in the study area, the area is divided in to 4 quadrants. The flora population in each quadrant is summed up for the total population in the study area. Field survey is done. Erukku, Aavarai and Nayuruvi are found in lease area. In the buffer zone, common trees like Neem, papaya, mango, teak, etc and shrubs like Avarai, Aloe vera, etc, climbers like Kovai, Jasmine etc are found.

FAUNA

In the study area, commonly found animals like dogs, cats, bush rat, cows, birds like crow, Myna, Sparrow, etc were found.

1.12 LAND USE

The land use land cover data is found using the LANDSAT – 9 satellite imagery. The number of bands used are 11. The land use pattern is given below:

Major Land Use Units of the Study Area in Percentage

Sl.No.	LAND USE / LAND COVER	Area in Sq.Km	Area in Percentage
1	Built-up land	6.42	2.03
2	Crop land	204.21	63.78
3	Fallow land	14.02	4.37
4	Land with scrub	18.89	5.89
5	Land without scrub	26.79	8.36
6	Hill & Forest	30.45	9.51
7	Plantations	5.1	1.60
8	Existing Quarry	2.56	0.80
9	Water bodies	11.73	3.66
	Total Area	320.17	100.00

1.13 SOCIO ECONOMIC ENVIRONMENT

The socio-economic environment of the study area is studied by conducting primary sites through site visits and conducting sample surveys. The secondary data obtained from Census 2011 is also used.

The following data area collected from secondary data.

- Demographic pattern.
- Health pattern
- Occupational structure.
- Amenities available.

The expert visited nearby villages in the study area. Discussions were held with the people from nearby locality to study the social and economic conditions prevailing in the area. The expert also visited nearby hospitals, primary health centres. The following observations were made.

The following observations were made.

Primary and higher secondary schools are available in many villages. For hospital facilities, people in the locality have to go to hospital in perambalur.

1.14 HYDROGEOLOGY OF THE LEASE AREA

The area is studded with few tanks that serve as the source for agriculture and also their surplus feeds adjoining tanks. The quarrying activity will not intersect ground water table as quarrying is proposed upto a depth of 56 m AGL and water table is found at a depth of 67 m BGL.

There are some tanks located in the study area, which are mostly dry throughout the year. These tanks get water only during monsoons. The factors may be monsoon failure, insufficient rainfall, poor rain water management and water consuming patterns.

1.15 GROUND WATER STUDY

For Ground water study, satellite imagery is used. Water levels from monitoring levels are collected through imaging. The pre-monsoon and post-monsoon data are collected and the results are analyzed.

As far as the mining lease area is considered, the area is rocky and no major seepage is envisaged. The production quantity is very less and the depth proposed is 56 m

AGL. Hence, there will not be any major impact due to mining on water levels or ground water levels in the area.

ANTICIPATED ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES

Environmental impacts on the following environments are identified.

- Land environment
- Water environment
- Vegetation
- Fauna
- Air environment
- Noise environment
- Socio-economic impacts

1.16 LAND ENVIRONMENT: IMPACT AND MITIGATION MEASURES

The major impact due to this project on land environment is the change in land use. Since this quarry is a small one and the production is less, mining activity will be carried out upto 56m Above Ground Level. Other than quarrying of minerals, no other change will be done since there is no dumping. To prevent soil erosion during monsoon season, garland drain will be constructed with silt traps. At the mine closure stage, 1.61.00 Ha of lease area will be left as rain water harvesting pond. 0.57.0 Ha will be developed with green belt. For this, plants like Pongamia pinnata, Syzigium cumini, Albizia lebbeck, Thespesia populnea, Bauhinia racemose, Cassia siamea, Azadirachta indica are selected. A total of 570 trees are planned to be planted. Spacing will be 3m x 3m.

1.17 WATER ENVIRONMENT: IMPACT AND MITIGATION MEASURES

Nanthai River- 3.60 km (SW) & Uppar River- 4.80 km (SE) is found nearby the lease applied area. The area is studded with few tanks that serve as the source for agriculture and also their surplus feeds adjoining tanks. The rainfall over the area is moderate, the rainwater storage in open wells, trenches is in practice over the area and the stored water acts as source of freshwater.

Since the mining operation will be limited upto depth of 56m AGL, there will not be any seepage. However, the rain water percolation and collection of water from seepage shall be less than 300lpm and it shall be pumped out periodically by a stand by diesel powered Centrifugal pump motivated with 7.5 H.P. Motor. The quality of water is expected to be potable. Hence, water stored in the quarry pit will be pumped into the adjacent agricultural fields. Further the water can also be used for plantation purposes

The major water bodies found in the buffer zone are Tank-150m(SW), Tank-260m(SE), Maruthandi Lake – 1.65km (W), Therani Big Lake-3.16Km(E), Pudukurichi Lake – 2.80 km (NE), Nanthai River- 3.60 km (SW), Uppar River- 4.80 km (SE) of the lease applied area. There are some Water bodies (River, Pond, Lake, Odai, Channel, etc.) within a radius of 500m.

Since these water bodies are located outside the lease area and there is no discharge of effluent or any untreated water from the mines will be made in to these water bodies, there is no major impact. The proponent will restrict the mining operation only within the lease and no other work will be carried out near the water bodies or any area outside the lease.

It is planned to carryout appropriate rainwater harvesting schemes and artificial recharge schemes in the area.

- Rain water falling in the quarry will be collected efficiently through garland drains.
- Water thus collected will be passed through collection tank with silt traps. This water can be used by the proponent for water sprinkling and for green belt purposes.
- Excess water after desiltation will be provided to downstream users, if any

1.18 BIOLOGICAL ENVIRONMENT: IMPACT AND MITIGATION MEASURES

Impacts

- Fauna is affected due to noise and vibration.

- Dust generation due to mining activities
- Change in land use of the lease area
- Accidental falling of animals

Mitigation measures

- Sirens will be blown before blasting in the mines. To reduce noise levels, plantation will be done. Blasting will be carried out only in the allotted time.
- To reduce dust generation, mist sprayers will be used. During transportation, the material will be covered with tarpaulin. Water sprinkling will be done to reduce generation of pollutants
- After the mine closure stage, the mine pit will be left as rain water collecting tank, which can attract bird population in the nearby areas.
- To prevent entry of animals, the mining area will be properly fenced.

1.19 AIR ENVIRONMENT: IMPACT AND MITIGATION MEASURES

The major air pollutants due to mining operations are fugitive emissions like PM₁₀, PM_{2.5}. Other than these pollutants, gaseous emissions of sulfur dioxide (SO₂) and oxides of nitrogen (NO_x) due to excavation/loading equipment and vehicles plying on haul roads are the cause of air pollution in the project area.

The major impacts are Dust emission due to drilling, blasting and transportation. The major mitigation measures include Using Wet drilling methods, Allowing drilling only with PPE, Carrying out blasting only during specified times, Avoiding blasting during unfavourable weather conditions, Using explosives of good quality, Using mist sprayers Regular wetting of transport, Covering the materials carried in tippers with tarpaulin, Proper maintenance of vehicles used for transportation, Conducting regular emission tests for vehicles used for transport Development of greenbelt is proposed in the safety zone of 7.5m barriers in the lease area.

The anticipated data is calculated using AERMOD software and the projected values are found to be within limits.

1.20 NOISE ENVIRONMENT: IMPACT AND MITIGATION MEASURES

Impacts

- ✚ Noise generation in mining is due to operation like drilling, blasting and transportation of minerals within and outside the lease area.
- ✚ As per DGMS (Directorate General of Mines Safety) and OSHA (Occupational Safety and Health Administration) limits, the acceptable noise level is 90 dB(A) for an exposure period of 8 hours.
- ✚ Exposure to loud noise can also cause high blood pressure, heart disease, sleep disturbances, and stress. Noise pollution also impacts the health and well-being of wildlife.
- ✚ Noise exceeding prescribed limits may cause impairment like abnormal loudness perception, tinnitus, which causes a persistent high-pitched ringing in the ears, paracusis or distorted hearing.

Mitigation measures

- ✚ As the distance between the source and receptor increases, the noise level also decreases. Hence, there will be a natural attenuation
- ✚ The proposed has planned to develop green belt in the periphery of the lease area, which diminishes sound volume by dampening them.
- ✚ All the equipment/machinery/trucks involved will be properly maintained to control noise generation
- ✚ Conducting regular health checkups for employees involved
- ✚ Employees will be made to work on shifts to reduce their exposure time
- ✚ Providing earplugs to all employees

By adopting these measures, the noise levels will be maintained well within MoEFCC limits since the baseline value is low.

VIBRATION: IMPACT AND MITIGATION MEASURES

Impacts

- ✚ Though vibration will be only felt by the people working inside the lease area, it is usually undesired.
- ✚ Vibration may also cause flyrocks
- ✚ It may frighten the birds and small insects in the lease area. However, it will be felt only for a short period

Mitigation measures

- ✚ Carrying out blasting on limited scale, only from 12:00 PM to 2:00 PM
- ✚ Control of fly rock and vibration by maintaining peak particle velocity with in standard as prescribed by the DGMS and MOEFCC.
- ✚ Shallow depths jackhammer drilling and blasting is proposed to be carried out with minimum use of explosive
- ✚ Supervising blasting by competent and statutory foreman/ mines manager

1.21 SOCIO ECONOMIC ENVIRONMENT

Impact and Mitigation measures

No land is acquired from anyone. No rehabilitation is needed. Hence, there is no negative impact. The proponent has planned to spend INR 5,00,000 for CER activities. This amount will be subjected to change after public hearing.

1.22 OCCUPATIONAL HEALTH

Impacts

Dust generation due to drilling and blasting, Noise generation due to drilling and blasting, unexpected accidents. Continuous exposure to dust causes Pneumonia, Tuberculosis, Rheumatic arthritis and Segmental Vibration, Short term impact will be lack of sleep, high blood pressure and heart ailments. Long term exposure may lead to partial or permanent deafness, Risks include fly rocks, cracks or fissures due to improper mining methods

Mitigation measures

- Using dust suppression measures like water spraying on roads to reduce rise of air pollutants
- Providing green belt for air pollutant and noise attenuation
- Ensuring slope stability
- Employing only trained professionals for blasting
- Conducting Pre-Medical Examination for employees before inducting
- Conducting periodical Medical Examination once in 6 months.
- Making all first aid kits available in mines office
- Keeping fire extinguisher in place
- Educating the employees about how to handle unexpected happenings
- Posting information containing emergency contact numbers in mines office
- By adopting all these measures, the safety of the employees working in the quarry will be ensured.

1.23 ENVIRONMENTAL MONITORING PROGRAMME

Monitoring is done to measure the efficiency of control measures implemented. Regular monitoring of various environmental parameters like air, water, noise and soil environments is needed to assess the status of environment during the project operation. A schedule is framed with timeline to monitor various parameters during the operation of the project. To evaluate the effectiveness of environmental management programme, regular monitoring of the important environmental parameters will be taken up. Air monitoring will be carried out once in 3 months, water sample will be collected once in a season, noise will be monitored once in 3 months, soil samples will be analyzed once per season. For EMP, a budget of INR 36.99 (10 years) Lakhs is allocated.

1.24 PROJECT BENEFITS

Financial benefits

- This project will contribute financially through payment of taxes like royalty, GST, etc.,
- The project will also contribute via CSR.
- The demands of people during public hearing will also be considered by the project proponent

Social benefits

- This project provides employment to 29 people directly. Local people will be hired for unskilled labour.
- Through CSR, nearby schools, hospitals will be benefitted.
- For CSR, INR 5,00,000 is allocated.
- Based on the demand of the people during public hearing, further funds will be allocated, if necessary.
- Various aspects of mining activities were considered and related impacts were evaluated. Considering all the possible ways to mitigate the environmental concerns Environmental Management Plan was prepared and 36.99 lakhs for the five years has been allocated as EMP cost. The EMP is dynamic, flexible and subjected to periodic review. For project where the major environmental impacts are associated, EMP will be under regular review. Thus, the proper steps will be taken to accomplish all the goals mentioned in the EMP and the project will bring the positive impact in the study area.



ANNEXURE-1

Rc.No.128/G&M/2025, Dated:29.04.2025

Department of Geology & Mining
Collectorate,
Perambalur - 621212



PRECISE AREA COMMUNICATION LETTER

Sub: Mines and Minerals - Perambalur District - Rough Stone e-Tender cum auction conducted on 27.03.2025 under Tender ID: 2025_CGAM_525779_1 - M/s.SR Mines and Minerals (BID ID:1274716) quoted highest Bid amount (H1) For the quarry listed in Serial Number 28 - Declared as H1 bidder - H1 Bid Amount remitted - Solvency Certificate submitted - Precise Area Communicated - Reg.

- Ref:
1. G.O.(Ms).No.21, Natural Resources (MMC.1) Department. Dated 31.07.2024
 2. Perambalur District Gazette (Extraordinary) Notification No.1, dated:18.02.2025.
 3. E-Tender published under Tender ID:2025_CGAM_525779_1 in Tamil Nadu Governmente-tender portal.
 4. Notice issued by the Assistant Director of Geology and Mining, Perambalur in Rc.No.128/G&M/2025, dated:28.03.2025 (to remit 10% of highest bid amount)
 5. Remittance challan No. 20250329003743 dated: 29.03.2025 submitted by M/s.SR Mines and Minerals (BID ID:1274716)
 6. Notice issued by the Assistant Director of Geology and Mining, Perambalur in Rc.No.128/G&M/2025, dated 01.04.2025 (to remit remaining 90% of the bid amount)
 7. Remittance challans dated:19.04.2025 & 23.04.2025 submitted by M/s.SR Mines and Minerals (BID ID:1274716)

I invite your attention to the references cited above

Notice Inviting Tender (NIT) was published vide Perambalur District Gazette Extraordinary Notification No.1, dated.18.02.2025, inviting applications for grant of rough stone quarry leases in Government poramboke lands in Perambalur District through e-Tender cum Auction. Online tender was published in Tamil Nadu Government e-tender portal (<https://tntenders.gov.in/>) under Tender ID:2025_CGAM_525779_1 and e-Auction was conducted on 27.03.2025 for the bidders whos' bids were qualified technically and financially.

After Financial Evaluation, M/s.SR Mines and Minerals (BID ID:1274716) was declared as H1 bidder for the quarry listed in Serial Number 28 of the Gazette as the firm quoted highest bid amount of Rs. 10,01,00,000/- for the said quarry. The H1 bidder was directed to remit 10% of the Highest bid amount vide notice in the reference 4th cited and accordingly, the H1 bidder remitted 10% of the bid amount to a sum of Rs. 1,00,10,000/- and submitted remittance challan No. 20250329003743 dated 29.03.2025 to this office.

Subsequently, M/s.SR Mines and Minerals (BID ID:1274716) was directed to remit the remaining 90% of Highest bid amount after adjusting the Bid Security already paid by them within one month to Government head of account and to submit original remittance challan to this office. Accordingly, M/s.SR Mines and Minerals (BID ID:1274716) has remitted Rs.8,64,96,710/- after deducting Rs.35,93,290/- (the Bid Security amount already paid by the bidder) in Government account within one month and submitted remittance challans to this office.

The details of H1 Bidder for the quarry listed in Serial No.28 of the District Gazette, H1 Bid Amount offered and remittance of Bid amount by bidder are as follows.

1. Quarry Detail	
Serial No. in District Gazette No.01, dated 18.02.2025.	28
Taluk	Alathur
Village	Padalur(E)
S.F.No.	10/1 Block 6
Extent	2.20.0 Hectares
Lease Period	10 Years
2. H1 Bidder, Bid Amount Remittance	
H1 Bidder	M/s.SR Mines and Minerals (BID ID:1274716) Flat No.2/1, Room No.4, Ramanujam Building, V.N Nagar, Karur Bibass Road, Trichy-620002.
H1 Bid Amount	Rs. 10,01,00,000/-
10% of H1 bid amount remitted	Rs. 1,00,10,000/- (Challan No. 20250329003743 dated:29.03.2025)
Bid Security (EMD) already remitted	Rs. 35,93,290/-
90% of bid amount paid after adjusting Bid Security already paid	Rs. 8,64,96,710/- (Challan No. 20250419010183 dated:19.04.2025 Challan No. 20250423004102 dated:23.04.2025)

The H1 Bidder, M/s.SR Mines and Minerals (BID ID:1274716) has remitted entire H1 Bid Amount of Rs. 10,01,00,000/- in Government account within one month as per sub- rule 16 of Rule 8 of the Tamil Nadu Minor Mineral Concession Rules, 1959.

Therefore, in exercise of the powers conferred under sub rule 17(a) of Rule 8 of the Tamil Nadu Minor Mineral Concession Rules, 1959, an extent of 2.20.0 hectares of Government land in S.F.No. 10/1 Block 6 of Padalur(E) Village, Alathur Taluk, Perambalur District as notified in Serial Number.28 of the Perambalur District Gazette (Extraordinary) Notification No.1, dated: 18.02.2025 is hereby fixed as Precise Area for grant of permission to quarry Roughstone for a period of 10 years to M/s.SR Mines and Minerals (BID ID:1274716), subject to the following conditions.



1. 10 meters safety distance should be left out for the adjacent Government lands.
2. The applicant shall not make any hindrance to the adjacent lands and public.
3. The applicant should submit approved Mining Plan, Environment Clearance and Consent to Establish (CTE) & Consent to Operate (CTO) issued by competent authorities for grant of quarrying lease in the subject area.

The applicant M/s.SR Mines and Minerals (BID ID:1274716) is directed to submit draft Mining Plan for the above area within 90 days for the approval of the Assistant Director, Geology and Mining, Perambalur and to submit Environment Clearance obtained from SEIAA, Tamil Nadu and CTE & CTO issued by the Tamil Nadu Pollution Control Board subsequently for further action.

Encl: Map showing the proposal lease area.

[Signature]
29/04/25
Assistant Director,
Geology and Mining,
Perambalur.

To
M/s.SR Mines and Minerals
(BID ID:1274716)
Flat No.2/1, Room No.4,
Ramanujam Building,
V.N Nagar,
Karur Bibass Road,
Trichy-620002.

[Signature]
29/4/25

Copy to:

1. The Chairman,
SEIAA Level Environment Impact Assessment Authority,
Panagal Maligai, Saidapet,
Chennai.
2. The Commissioner of Geology and Mining, Chennai-32.



ANNEXURE-2

From

Thiru D.Bernard, M.Sc.,
Assistant Director,
Geology and Mining,
Perambalur.

To

M/s.SR Mines and Minerals
Flat No.2/1, Room No.4,
Ramanujam Building,
V.N Nagar,
Karur Bypass Road,
Trichy-620 002.

Rc.No.128/G&M/2025, Dated:12.05.2025

Sir,

Sub: Mines and Minerals - Perambalur District - Rough Stone -
e-Tender cum auction conducted for Roughstone quarries in
Government lands - M/s.SR Mines and Minerals quoted highest
Bid amount (H1) For the quarry in S.F.No. 10/1, Block-6, OAE of
2.20.0 hectares in Padalur(East) Village, Alathur Taluk -
Declared as H1 bidder - H1 Bid Amount remitted - Precise Area
Communicated - Draft Mining Plan submitted for approval -
Approved - Reg.

- Ref:
1. G.O.(Ms). No.21, Natural Resources (MMC.1) Department,
Dated 31.07.2024.
 2. Perambalur District Gazette(Extraordinary) Notification No.1,
dated:18.02.2025.
 3. Notice issued by the Assistant Director of Geology and
Mining, Perambalur in Rc.No.128/G&M/2025, dated:
28.03.2025
 4. The Assistant Director, Geology and Mining, Perambalur
Precise Area Communication letter Rc.No.128/G&M/2025,
dated 29.04.2025.
 5. M/s.SR Mines and Minerals, letter dated. 09.05.2025.

Tender cum Auction for grant of Roughstone quarries in Government lands notified in Perambalur District Gazette Extraordinary Notification No.1, dated.18.02.2025 was conducted through online as per Rule 8 of the Tamil Nadu Minor Mineral Concession Rules, 1959.

M/s.SR Mines and Minerals was declared as Highest Bidder for the quarry in S.F.No. 10/1, Block-6, to an extent of 2.20.0 hectares in Padalur(East) Village, Alathur Taluk, Perambalur District and the lease period proposed for the subject quarry is 10 years. The Highest Bidder, M/s.SR Mines and Minerals remitted entire highest bid amount and other statutory documents in time in accordance with rules and in the reference, 4th cited, precise area was communicated to firm with a request to submit Mining Plan for the approval of the Assistant Director, Geology and Mining, Perambalur District and Environmental Clearance obtained from SEIAA for further process.

Accordingly, in the reference 5th cited, the successful bidder has submitted 3 copies of Draft Mining Plan prepared by Qualified Person for the above area. The draft

Mining Plan submitted by M/s.SR Mines and Minerals, has been scrutinized as per extant rules and guide lines / instructions issued by the Commissioner of Geology and Mining, Chennai in the letter Rc.No.3868/LC/2012 dated. 19.11.2012. The following observations were made in scrutiny.

- a. 10-meter safety distance is earmarked for the adjoining Government lands.
- b. The Geological reserve of Rough stone in the subject area has been assessed as 27,00,156 metric tonnes.
- c. The mineable reserve has been computed as 16,30,681 metric tonnes of Rough stone up to a depth of 56m (above ground level)
- d. The lease period of the subject Rough stone quarry is 10 years and it has been proposed for the production of 9,80,993.75 metric tonnes of Rough stone for the first five years up to a depth of 56m(above ground level) and remaining quantity of 6,49,687.50 metric tonnes of Rough stone in ~~the~~ second five years.
- e. The depth of water table in the subject area is reported as 67m BGL and workable depth has been proposed to 56m(above ground level) in the mining plan. Hence, the quarrying operation will not affect the water table in the area.
- f. Drilling and blasting using jack hammers and shot hole blasting are proposed. Small dia, 25mm slurry explosives are proposed to be used for shattering and heaving effect for removal and winning of Roughstone. No deep hole drilling or primary blasting is proposed.
- g. It has been proposed to adopt controlled blasting measures for minimizing ground vibration and fly rocks.
- h. Machineries like Tractor mounted compressor attached with Jack hammers, excavators with rock breaker attachment are proposed for quarrying operation. Tippers of 5/10 Tons capacity are proposed for transportation.

4) The Mining Plan is prepared in accordance with the guidelines / instructions issued and tallies with the field conditions. The special conditions imposed in the precise area communication letter have been incorporated in the Mining Plan. Therefore, the draft mining plan is hereby approved subject to the following conditions.

- i. That the Mining Plan is approved without prejudice to any other laws applicable to the quarry area from time to time whether made by the Central Government, State Government or any other authority.
- ii. That the approval of the Mining Plan does not in any way imply the approval of the Government in terms of any other provisions of the Mines and Minerals (Regulations and Development) Amendment Act 2015 or Mineral (other than Atomic and Hydrocarbon Energy Minerals) concession Rules 2016, or Tamil

Nadu Minor Mineral Concession Rules, 1959 or any other laws including Forest (Conservation) Act 1980, Forest Conservation Rule, 1981, Environment Protection Act, 1980 and the rules made there under.

- iii. That the Mining plan is approved without prejudice to any other order or directions from any court of competent jurisdiction.
- iv. That the approval of Mining Plan does not confer any rights for the renewal of quarry lease.
- v. The approval is valid up to the subsistence of the lease period only.

Encl: 2copies of approved Mining Plan.

D. Ram
12/05/25
Assistant Director,
Geology and Mining,
Perambalur.

Copy to:

- 1. The Chairman,
SEIAA Level Environment Impact Assessment Authority,
Panagal Maligai,
Saidapet, Chennai.
- 2. The Commissioner of Geology and Mining, Chennai-32.

g. A.
12/05/25
12/5/25



ANNEXURE-3

From

Thiru D.Bernard, M.Sc.,
Assistant Director,
Dept of Geology and Mining,
Perambalur.

To

M/s.SR Mines and Minerals
Flat No.2/1, Room No.4,
Ramanujam Building,
V.N Nagar,
Karur Bypass Road,
Trichy-620 002.

Rc.No.128/G&M/2025

Dated: 16.05.2025

Sub: Mines and Minerals - Perambalur District - Rough Stone -
e-Tender cum auction conducted for Roughstone quarries in
Government lands - M/s. SR Mines and Minerals quoted highest Bid
amount (H1) For the quarry in S.F.No. 10/1, Block-6, OAE of 2.20.0
hectares in Padalur(East) Village, Alathur Taluk - Declared as H1
bidder - H1 Bid Amount remitted - Precise Area Communicated - Draft
Mining Plan submitted for approval - Details of quarries situated within
500 mts radial distance requested - furnished - Reg.

Ref: 1. G.O.(Ms). No.21, Natural Resources (MMC.1) Department, Dated
31.07.2024
2. Perambalur District Gazette(Extraordinary) Notification No.1,
dated:18.02.2025.
3. Notice issued by the Assistant Director of Geology and Mining,
Perambalur in Rc.No.128/G&M/2025, dated: 28.03.2025
4. The Assistant Director, Geology and Mining, Perambalur Precise
Area Communication letter Rc.No.128/G&M/2025, dated
29.04.2025.
5. M/s.SR Mines and Minerals letter dated 15.04.2025.

The applicant M/s. /SR Mines and Minerals, Perambalur in the reference 5th
cited has requested to provide the details of quarries situated within 500 mts
radius distance from the proposed lease area referred in the subject.

Accordingly, the details of quarries (existing, proposed, expired,
abandoned) situated within 500 mts radial distance from the subject area are
furnished below,

1)Existing quarries:

Sl. No	Name of the Owner	Taluk / Village	S.F.Nos	Extent	GO. No	Lease Period	Remarks
	Nil						

2)Proposed quarries:

Sl. No	Name of the Owner	Taluk / Village	S.F.Nos.	Extent	Lease Period	Remarks
1	M/s.SR Mines and Minerals Flat No.2/1, Room No.4,Ramanujam Building,V.N Nagar, Karur Bibass Road, Trichy-620002.	Alathur/ Padalur (East)	10/1 (Block 6)	2.20.0	-	Instant Proposal
2	Thiru. R.Rajkumar S/o. Rajaram, No.4C, 4 th floor, Sivam Sri Madhav, Kuttimani Nagar, Pichandar kovil, Trichy-621 216.	Alathur/ Padalur (East)	10/1 (Block 1)	1.50.0	-	Presently proposed
3	Thiru.Hariharan. L No. 9, Dhanalakshmi Street Postal Nagar, Nemilicheri Chrompet, Kancheepuram District – 600 044.	Alathur/ Padalur (East)	10/1 (Block 2)	1.40.6	-	Presently proposed
4	Thiru.P.Velmurugan No.1, Royal mahalakshmi Nagar, Virudhachalam, Cuddalore -606 001.	Alathur/ Padalur (East)	10/1 (Block 3)	1.40.0	-	Presently proposed
5	M/s. Rajamalai Metals No. 3/350 H, Jeya Complex, Main Road, Padalur, Perambalur-621 109.	Alathur/ Padalur (East)	10/1 (Block 4)	1.40.0	-	Presently proposed
6	Thiru.M.Thangaraj S/o. Maran, No.158/34A, Abiramapuram west, Collector Office Road, Perambalur -621 212.	Alathur/ Padalur (East)	10/1 (Block 5)	2.10.0	-	Presently proposed
7	M/s.Mars Mines No.24/7, Padalur East, Alathur Taluk, Perambalur -621 109.	Alathur/ Padalur (East)	10/1 (Block 7)	1.30.0	-	Presently proposed
8	Thiru.Vinoth R 44/4 Subbramaniyyar Kovil street, Tittakudi, Cuddalore District-606 106.	Alathur/ Padalur (East)	10/1 (Block 8)	1.20.0	-	Presently proposed

9	M/s.Anjancyaa Minerals No.3/379J, Ward -08, Main Road, Irur, Alathur Taluk, Perambalur District - 621 109.	Alathur/ Padalur (East)	10/1 (Block 9)	1.20.0	-	Presently proposed
10	Thiru.P.Velmurugan No.1, Royal mahalakshmi Nagar, Virudhachalam, Cuddalore -606 001.	Alathur/ Padalur (East)	10/1 (Block 13)	1.00.0	-	Presently proposed

3) Expired quarries

Sl. No	Name of the Owner	Taluk / Village	S.F.Nos.	Extent	Lease Period	Remarks
1	Nil					

4) Abandoned quarries:

Sl. No	Name of the Owner	Taluk / Village	S.F.Nos.	Extent	Lease period
1	M.Baskaran, S/o.MuthuRediyar Thiruvalakuruchi, Padalur (East) Village, Alathur Taluk, Perambalur District.	Padalur(E) Alathur	4(1)(P),4(2) (P), 7(3)(P)	2.00.0	24.01.2018 to 23.01.2023
2	D.Sakthivel, S/o. P.K. Duraisamy, Perumal Kovil Street, Siruvachur, Perambalur.	Padalur(E) Alathur	10/1 Block No.13	1.20.0	16.05.2007 to 15.05.2012
3	K.Mathiyalagan, S/o.Kanagasabi, State Bank Colony, Kumbakonam.	Padalur(E) Alathur	10/1 Block No.18	1.00.0	23.05.2007 to 22.05.2017
4	B.Senthilkumar, S/o.P.Balagopal, 454,4 th Cross Road, Shanmugam Nagar, Uiyakondam,Thirumalai, Trichirappalli.	Padalur(E) Alathur	10/1 (Part)	1.00.0	12.04.2006 to 11.04.2016
5	M.Ravi, S/o.Muthukrishnan, No2/78, Malaiyadivaram, Chettikulam Post, Kunnam TK,Perambalur District.	Padalur(E) Alathur	10/1 Block No.20	1.00.0	11.05.2007 to 10.05.2017
6	R.Sureshbabu, S/o.V.Rajagopal, No.244, Philomina Nagar, 3 rd Street, Nanjikottai Road, Thanjavur.	Padalur(E) Alathur	10/1 Block 17	1.00.0	23.05.2007 to 22.05.2017

7	S.N.Vinoba, S/o. S.Nagarajan, 2/163, 2 nd cross , Lakshmipuram, Ariyamangalam, Trichy-10	Padalur(E) Alathur	10/1 Block 5	1.00.0	26.04.2007 to 25.04.2012
8	M.Raja, S/o. Muthusamy, No.211/1, Mannarpillai Street, Srirangam, Trichy-6	Padalur(E) Alathur	10/1 Block 3	1.00.0	07.06.2007 to 06.06.2012
9	D.Rajachithambaram, S/o. Duraisamy, No.236, Reddiyar Street, Sirdevimangalam, Manachanallur Taluk, Trichy District.	Padalur(E) Alathur	10/1 Block 6	1.00.0	11.05.2007 to 10.05.2012
10	V.Panneerselvam, S/o.Vcerasamy, South Street, Thennamanadu Post, Orathanadu Taluk, Thanjavur District.	Padalur Perambalur	10/1 Block 22	1.00.0	31.05.2011 to 30.05.2021

[Signature]
16/06/25
Assistant Director,
Geology and Mining,
Perambalur.

[Signature]
16/06/25